SANITARY DIVISION.

Notice is hereby given that quotations will be received in the office of the Executive Engineer, Sanitary Division, up to 4 P.M., on 28th July 1918, for supplying the following furniture within a month of the acceptance of the quotations. The successful competitor will be required to deliver the furniture at this office premises.

Items.	Per	Quantity
Drawing and Officers' tables with two drawers (5′×3′×2½′) ...	Each.	3
Chairs, rosewood, with arm, rattan bottom and back	"	5
Almirahs, teakwood (6′×3½′×1½′)	"	2
Stools, teakwood	"	6
Record boxes, teakwood (3′×2′×2½′)	"	5
Calling bells	"	2
Clocks	"	2
Alighar locks of 2½″ with duplicate keys	"	10
Rattan trays	"	5

Dated 9th July 1918.

It is hereby notified that a sum of Rs. 144-15-6, being the amount due to contractor Mr. N. Ramiah for diverting Storm Water Drain in Basavangudi Extension, is outstanding in the books of this office. If the same is not claimed by the party or claimant within three months from this date, the amount will be credited to Government.

N. SUBBA RAO,
Executive Engineer.

BANGALORE DIVISION.

Abstract Notification.

Attention is invited to the notification published in Part IV of the *Mysore Gazette*, dated the 11th July 1918, calling for tenders for the purchase of burnt stone slabs at Silledar Lines, Bangalore.

C. VIJAYARANGAM NAIDU,
Executive Engineer.

MYSORE DIVISION.

Notice.

The attention of the public is invited to the advertisement in detail, published in the *Mysore Gazette*, dated 4th July 1918, calling for tenders for restoring the Ankushapur Minor Tank, Mandya Taluk.

Y. ASVATHANARAYANA RAO,
Executive Engineer.

SHIMOGA DIVISION.

Abstract Notification.

The attention of the public is invited to the notification calling for tenders published in page 605, Part IV of the *Mysore Gazette*, dated 4th July 1918, for constructing Groynes on the left bank of the Tunga river, near Seegehatty at Shimoga.

V. R. NIJAGAL,
Executive Engineer.

KADUR DIVISION.

Dated 13th July 1918.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, up to 5th August 1918, for constructing a District Forest Office at Chikmagalur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 30th, 1920.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chikmagalur, between the hours of 11 A.M. and 5 P.M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. (300) in cash or Government Promissory Notes as earnest money, and be superscribed "Tender for constructing a District Forest Office at Chikmagalur," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract of detailed quantities for constructing a District Forest Office at Chikmagalur.

No.	Items of work	Per	Quantity
1	Earthwork excavation for foundation and filling in basement	C. yd.	235
2	Concrete in chunam	C. ft.	2,548
3	Burnt stone in chunam	"	5,324
4	Burnt brick in chunam	"	6,159
5	Do archwork	"	853
6	Burnt stone slab dressed 3" to 6"	S. ft.	1,152
7	Plastering with chunam	Sq.	95·14
8	White and colourwashing	"	95·14
9	Pointing with cement	"	8·00
10	Teakwood work wrought and put up including wood oiling	C. ft.	187·74
11	Roofing with 1st class Mangalore tiles with teak reepers to be oiled	Sq.	17·61
12	Roofing with 1st class Mangalore tiles with ceiling tiles, teak reepers with wood oiling.	"	20·87
13	Mangalore ridge tiles set in mortar and pointed with cement	R. ft.	129
14	Mangalore glass tiles	No.	6
15	Teakwood plant, ½" thick for valleys with wood oiling	S. ft.	174
16	Zinc sheets for valleys with chunam borders	"	174
17	Teakwood panelled door with silicate painting	"	312
18	Teakwood panelled windows with iron bars and clamps glazed shutters inside and silicate painting.	"	1234
19	Teakwood flat ventilators with glazed shutters, iron bars, clamps and silicate painting.	"	90
20	Teakwood circular ventilators with glazed shutters, etc., complete	S. ft.	15
21	Teakwood panelled screen with frames, hinges, doorway, oiling	No.	294
22	Cut stone pillars nicely dressed with caps and bases, etc.	Sq.	17
23	Flooring with 9" square Mangalore tiles on 3" concrete bed and cement pointing.	"	10·88
24	Flooring with Cuddappah slabs on 3" concrete bed and cement pointing, etc., complete.	"	9·52
25	Teakwood ornamental eave board with painting	R. ft.	4·58
26	Tarring wood work	L. S.	Rs.
27	Teakwood pendant with painting	No.	22
28	Teakwood finials	"	4
29	Teakwood large board	"	1
30	Sham windows and ventilators in front verandah	L. S.	Rs.
31	Opening out approach road and gravelling and filling in earth in low portions, etc.	"	"
32	Constructing tunnel and clearing site, etc.	"	"
33	Constructing a masonry latrine with a doorway, etc.	"	"
34	Teakwood stands for keeping tents	"	"
35	M. & S. M. Railway purlin	R. ft.	29
	Iron Record Racks.		
1	Iron base for vertical frames with painting	No.	20
2	Angle iron vertical frames do	lbs.	2,585
3	Flat iron bars	"	932
4	Drilling holes and cutting frames, etc.	No.	712
5	Rivets	"	600
6	Teakwood ladder with painting	L. S.	Rs.
7	Sundry works and unforeseen	"	"

K. PONNAPPA,
Executive Engineer.

DISTRICT, MUNICIPAL AND LOCAL BOARDS.

BANGALORE CITY MUNICIPALITY.

Notice dated 8th July 1918.

Sealed tenders for supplying the following articles of furniture will be received by the undersigned in the Municipal Office up to 31st July 1918.